



Jukebox Implementation

Thank you for your participation in the Jukebox program. We offer a complete installation package specifically tailored for your Applebee's locations. Below is a brief description of the installation process.

We start the installation at 7Am. We need this early time to start because it takes about 3.5 to 4 hours to complete the install process with about 30 minutes of training. We prefer the GM to be there.

- 1) As part of the install, we craft a custom wood package that blends into the wood colors of the restaurant and hides all wiring.
- 2) We install a speaker package (3 ceiling or 4 Bose) speakers depending on the ceiling type (See installation survey). The speaker package is wired to the jukebox.
 - A) For the drop ceiling stores we install 3/3-way ceiling array speakers. These speakers are the same size as the ceiling tiles (2'x 2'). When facing the front of the bar we place a speaker on the right and left side with the third speaker at the crown of the bar.
 - B) For the open ceiling concept, we install 4 Bose 301 speakers above the bar drop ceiling. All speakers are secured.
- 3) The next part of the process is to run 2 or 3 cat5 cables to the office. One is for the internet and one or two that interface the house music system to the jukebox. When someone pays for a song, the system mutes the Background Music, then plays the song through the jukebox speaker package and your house system at the same time. When the song ends the background music initiates.
- 4) Finally, we program your Franchise's music requirements and train the GM on its functionalities and light maintenance requirements. SNC will supply a remote, promotional material, and service contact cards.

If you should have any questions please call us,

Contact

Fred Cyrway "The Jukebox Man"

281-797-0059

www.servicenovelty.com